

Acton Precast Concrete Limited

Custom Sized Precast Sheds

Manufactured in panels and assembled on site, our custom sized sheds can be made to accommodate a wide range of options and designs. All units are produced under factory conditions using high quality methods and materials. The exposed aggregate exterior walls provide a decorative and durable finish that blends in to almost any environment. Fire rated steel doors with cast in frames keep out the elements, both environmental and criminal. These units are made to order and can be assembled by our site crew in about six hours.

Specifications:

- Concrete: 35 mpa, air entrained to 5-7% - manufactured to CAN/CSA-A23.1
- Reinforcing steel Grade 400W
- Panel connections made using PSA plated inserts and galvanized steel brackets
- Joints between panels sealed with Sicaflex A1A (limestone)
- Roof and floor slabs interlock wall panels for positive structural connection
- Galvanized steel door c/w deadbolt and finger pull for tamper resistance
- All door hardware, commercial grade, tamperproof, stainless steel
- 2 6" diameter vents with aluminum louvered grills
- Optional double doors, openings for power vents, ductways, windows, available

For more information, please contact our office at sales@actonprecast.com or 1-800-461-1516

